

13 Key Issues to Keep In-Mind when Selecting a Method for Distributing Electrical and Mechanical Services in a Data Center

Planning to build a new data center?

It may come as a surprise, but one of the first and most critical and often overlooked decisions you'll have to make, is how to distribute mechanical and electrical services to the cabinets. What you choose will affect the operational effectiveness, efficiency, and economics of the facility over its lifetime.

| Check the Items You Find Important and /or Interesting | | | | | | |
|--|---|---|--|---|--|---|
| | Conventional Raised Floor (CRF) | ✓ | On-Slab Flooded Room | ✓ | Interstitial's Electro-Mechanical | ✓ |
| #1: Optimization of the Building Design and Floor Space Space is Gold and Cabinets are Diamonds | Excess Space Req'd Due to # of Cooling Units and Their Spacing | | Buildings Need to be Larger Due to Cooling Equip. & Aisle Spacings | | Optimizes Space Can Reduce White Space Up to 30% | |
| #2: Effective Cooling of Servers Cooling servers is costly...even more costly when they aren't cooled efficiently | More than 50% of Server Fans Must Work Harder & Cabinets Over 5 kW a Challenge | | Server Fans Work Harder: 32.6% for 9 kW when Using Cold Aisle Containment | | 100% of Servers have Required Air Anywhere in the Room | |
| #3: Precision Air Distribution There's little value to precision cooling equipment unless there's a precision means of delivering that cooling. | Obstructed Underfloor Prevents Predictable Airflow | | No Control of Air Flow in the Individual Aisles for Varying Cabinet kW | | Precise Air Delivery Anywhere in the Entire Room. Adjustable at Every Cabinet | |
| #4: Power Distribution There are 2 ways to distribute power--overhead or underfloor. | <u>Underfloor or Overhead</u> Underfloor Congests Airflow--Plenum Rated Wire Required | | <u>Overhead Only</u> Costly to Install Adds Load to Roof Working from Ladders | | <u>Underfloor</u> Easier and Faster to Deploy and Manage | |
| #5: Structured Cable Distribution There are only 2 ways to install structured cable --overhead or underfloor | <u>Overhead or Underfloor</u> Underfloor Congests Airflow--Plenum Rated Cabling Required | | <u>Overhead Only</u> Costly to Install Adds Load to Roof Working from Ladders | | <u>Overhead or Underfloor</u> Underfloor Easier and Faster to Deploy and Manage | |
| #6: Containment Containing the hot and cold air from one another... | <u>Optional</u> But, Generally Preferred | | <u>Mandatory and Costly</u> Complicates Work for Operations Staff | | <u>Not Required</u> Simplifies Installation and MAC | |
| #7: A/C Redundancy Uptime is critical and downtime a catastrophe | Effective Redundancy is Unachievable Because of A/C Zone Limitations | | Almost Non-Existent because of A/C Units Relation to Aisles | | Effective N+1 | |
| #8: MAC Moves, Adds and Changes are Inevitable | Complicated Due to Containment and Access to Wiring | | Changes Can be Messy if Sprinklers, Lighting & Smoke Detectors Moved | | Simple Changes of Air, Power and Cables | |
| #9: Deployment Time The quicker the better... | Average Design and Build Time | | Longer Engineering & Inst. Time Due to A/C, Containment and Wiring | | Easier Engineering and Faster Deployment | |
| #10: Floor Slab Loading Concrete and steel are costly | 312 # per sf for 2,500 # Cabinets | | 312 # per sf for 2,500 # Cabinets | | 189 # per sf for 2,500 # Cabinets | |
| #11: Roof Reinforcement Reinforcing the roof structure is costly whether an existing or a new roof | Only Required if Overhead Distribution of Wires and Cables | | Mandatory | | Not Required | |
| #12: Seismic This isn't an issue unless you're in an earthquake zone | Special Reinforcement | | Special Reinforcement | | Inherent for Most of North America | |
| #13: Installation of Piping and Hoses This is mandatory for liquid cooling systems | Possible, but Costly and Obstructs Airflow | | Cannot be installed over ITE per NFPA-75 | | Simple in the Upper Utility Plenum | |

* For a more detailed explanation of these 13 points please contact us.

Interstitial Systems developed Interstitial as a holistic solution to solve the problems associated with the effective and efficient operation of the modern data center. It is a comprehensive system that not only addresses distribution issues, it goes beyond that, making related issues simpler and operationally better than conventional methods.

